

Schedule of work					
Name of Work: EI work for installation of AFM in the ground floor of CCRES building					
Sl.No	Item description.	Quantity.	Unit.	Rate.(Rs.)	Amount(Rs.)
1	Supplying and fixing DP sheet steel enclosure on surface/recess along with 20,25/32 A ,240 V 'C' curve DP MCB complete with connections,testing and commissioning etc.as required.	2	Nos.		
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor,single core cable in surface/ recessed medium class PVC conduit as required.				
a)	2X4 sq.mm. + 1 X 4 sq.mm earth wire.	12	Metre		
3	Supplying and fixing following switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc.as required.				
a)	15/16 A switch.	4	Nos.		
b)	6 pin 15/16 A socket outlet.	4	Nos.		
4	Supplying and fixing following size/modules,GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a)	6 module (200 mm X 75 mm)	2	Each		
				Total :	
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
GST No:					
HSN/SAC code:					
CGST@ 9% considered in the above BOQ					
SGST@ 9%Considered in the above BOQ					