

Schedule of work

Dedicated earthing for Room No.: 4 in Biology Building

SI No	Item	quantity	unit	Rate	Amount
3	Proviing and fixing 50 mm X 5mm copper strip on insulator surface for connections etc.as required.	1	Metre		
4	Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories and providing masonary enclosure with cover plate having locking arrangement and watering pipe of 2.7m long etc. with charcoal/coke and salt as required.	2	Set		
5	Providing and fixing 25mm x 5mm copper strip (wrapped with PVC sleeve) in 40mm dia G.I. pipe from earth electrode including connections with bruss nut,bolt,spring,washer excavation and re filling etc as required.	55	Metre		
				Total	
Rupees.....Only					
NOTE: The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
GST No:					
HSN/SAC code:					
CGST@ 9% considered in the above BOQ					
SGST@ 9%Considered in the above BOQ					