

Schedule of Work						
Name of Work: Electrical Renovation Work for Room No. 43 situated in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group C (as per CPWD Categorisation)	5	Point			
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
a)	2X1.5 sq.mm+ 1X1.5 sq.mm earth wire	10	Metre			
c)	2X4sq.mm +1X4sq.mm earth wire	120	Metre			
3	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required.					
a)	2 Module	6	Nos			
(c)	6 Module	5	Nos			
4	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.					
a)	6 pin 15/16A Socket	13	Nos.			
b)	15/16 amp switch	10	Nos.			
c)	Telephone socket outlet	1	Nos.			
5	Supply 40W,4' feet wall mounting type LED double tube light fitting (as per Philips Smartbright waterproof Cat.No.WT200CLED40S6500/PSUL120/4000PSUL60 with LED tube or equivalent model) complete with all accessories including connection with 1.5 sq.mm FRLS PVC insulated copper conductor ,single core cable and earthing etc. as required	5	Nos.			
6	Installation, testing and commissioning of pre-wired, LED fitting / compact Led fitting of all types, complete with all accessories and tube etc. directly on ceiling, including connection with 1.5sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	5	Nos.			
7	Supplying & Fixing of modular type 20Amp A.C. starter switch with GI Box complete recessed in wall.	3	Nos.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
8	Supply & fixing of telephone hand set as per cat. No-6390 or technically equivalent model of other approved manufacturer (make -Panasonic TS400SX /Beetel	1	No.			
9	Supply & fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc.as required	2	No.			
				TOTAL		
	Rupees:-					
	SGST%					
	CGST%					
i)	GST No.					
ii)	SAC No.					
iii)	Enclosed GST registration certificate copy					
	Note:-The quoted rate shall be inclusive of all taxes& duties,levies,cess etc and GST also.Nothing extra will be paid to the Contrctor except the accepted rate.i,ii,iii is mandetory.					